

# California Fish Passage Advisory Committee Connectivity Case Studies

June 17, 2020

[www.cafishpac.org](http://www.cafishpac.org)



# Presenters



## Cedar Creek

Kristine Pepper, P.E. – Caltrans – North Region District 1 – Eureka




## Quiota Creek Restoration and Refugia Road

Tim Robinson, Fisheries Division Manager – Cachuma Operation and Maintenance Board



## Twin and Ditch Gulches

Eric Rulison Biologist – Caltrans – North Region District 2




# Cedar Creek

Kris Pepper, P.E.  
Department of Transportation  
North Region-District 1-Eureka




# Topics

- ▶ Project Location
- ▶ Purpose and Need
- ▶ Science and Data to Inform Project Goals
- ▶ Existing Facility
- ▶ Design
- ▶ Project Collaboration
- ▶ Permits and Approvals Required
- ▶ Construction
- ▶ Post Project Monitoring
- ▶ Lessons Learned
- ▶ Questions



# Project Location

Mendocino County @ Highway 101  
 Cedar Creek tributary to South Fork Eel River



# Cedar Creek Bridge – SR 271



# Existing Facility

- Constructed 1969
- 22' Concrete Arch Culvert
- 763' long
- 1.2% slope
- 24 steel armored concrete weirs
- Concreted RSP apron
- Denil Fish Ladder





# Purpose and Need Funding Source

- Purpose and Need
  - Preserve the integrity of the culvert invert
  - Remove barriers to the migration of fish – SB 857
- Funding
  - Initiated by Structure Maintenance and Investigations (SMI),
  - Funded through the State Highway Operations and Protection Program



# Science and Data Used to Inform Project Goals

- CDFW PAD – Barrier Status/Species
- California Department of Transportation (Caltrans) District 1 Pilot Fish Passage Assessment Study: Volume 1 – Overall Results (2005)- AKA ‘Lang’ Study
- Topographic survey
- Geologic information
- Hydrologic
  - Basin transfer technique
  - Recurrence interval-Fish passage design flows
- District 1 Hydraulics Historic Files
  - Correspondence with CDFG
  - Correspondence internally
  - Past project design records/as-built plans
  - Construction photographs
  - Institutional knowledge-staff
- Collaboration with resource agency staff
- Fish Passage Design guidance:
  - CDFW
  - Caltrans
  - NMFS
  - US Army Corps
  - USFWS
- Caltrans commissioned study: Influence of Fish Passage Retrofits on Culvert Capacity (2008)
- Various other hydraulic engineering trainings, reports and circulars

# Species of interest

- Federally and State listed species:
  - coho salmon (*Oncorhynchus kisutch*),
  - Chinook salmon (*Oncorhynchus tshawytscha*) and
  - steelhead trout (*Oncorhynchus mykiss*)
- California Species of Special Concern/interest:
  - Pacific lamprey (*Entosphenus tridentatus*)
- Foothill Yellow-Legged Frog candidate for listing in July 2017



## Fish Passage Design Flows


<i>Target Species</i>	<i>Fish Passage Design Flows</i>	
	Low	High
Juvenile Salmonid	6.9	162
Adult Resident	8.6	274
Adult Salmonid	13.59	643

**Table 1-Fish Passage Design Flows**

# K- Phase Design – Project Initiation Document

## CEDAR CREEK ARCH CULVERT REPAIR & FISH PASSAGE RESTORATION

DESIGN STUDY ONLY





2014/04/17









STEP - POOLS


Overall channel slope 3.0-5%  
Maximum elevation drop 5ft/sequence  
Figure XII-24  
Step spacing 0.4 - 0.8 channel widths  
Pool spacing 2 - 4 channel width



**CEDAR CREEK ARCH CULVERT  
EA 01-0C3700  
STUDY OF WEIR DESIGN AND LENGTH**




# Downstream Channel Weirs –Stage 1






# Typical Lamprey and Salmonid Weirs




WEIRS F5-F12

## FISHWAY CONCRETE WEIRS TYPICAL SECTIONS



SECTION D-D  
LAMPREY WEIR DETAIL



SECTION E-E  
SALMONID WEIR DETAIL



# Project Collaboration

- Initiated by CT District 1 Bridge Preventative Maintenance Coordinator,
- CT Project Manager, Steven Blair, P.E.
- CT Project/Hydraulic Engineer, Kristine D. Pepper, P.E.
- CT Biologist, Gail Popham
- CT Environmental Coordinator, Jason Meyer
- NMFS Hydraulic Engineer, Margret Tauzer
- CDFW Biologist, JoAnn Dunn
- CDFW Hydraulic Engineer, Jonathan Mann, P.E.
- NMFS Biologist, Rebecca Bernard
- USFWS Biologist, Damon Goodman
- Bugler Construction, Glenn Bugler
- CT Construction Resident Engineer, Sheri Rodriguez, P.E.
- CT Environmental Construction Liaison, Jim McIntosh
- CT Construction Inspector, Jack Naylor





# Permits and Approvals Required

- U.S. Fish and Wildlife Service (USFWS)
  - Section 7 consultation for threatened and endangered species using a Programmatic Letter of Concurrence
- National Marine Fisheries Service (NMFS)
  - Section 7 consultation for threatened and endangered species
- US Army Corps of Engineers (USACE)
  - Section 404 of the Clean Water Act (CWA)
  - Project in compliance with Department of the Army Nationwide Permit (NWP) 27-Aquatic Habitat Restoration, Establishment and Enhancement Activities
- California Department of Fish and Wildlife (CDFW)
  - Section 1602 - Streambed Alteration Agreement and consistency determination with biological opinion prepared by NMFS
- North Coast Regional Water Quality Control Board
  - Federal Clean Water Act (CWA), section 401, Water Quality Certification

# Contractor Proposed Access



# Contractor Proposed Access



# Contractor Proposed Access



# Contractor Proposed Access




# Clearwater Diversion



# Clearwater Diversion



October 2017  
Downstream  
Fishway





Fishway Weirs  
Concrete Pour



October 2017  
Downstream Fishway




Lamprey  
Weir


Salmonid  
Weir

# Post Project

- Fishway completed October 2017
- Culvert weirs completed October 2018



# Downstream



THIS DRAWING IS HEREBY ACKNOWLEDGED TO BE PART OF THE PLANS REFERRED TO IN MY CONTRACT WITH THE STATE DEPARTMENT OF PUBLIC WORKS, DIVISION OF ARCHITECTURE.		DATE: 1/15/19 CONTRACTOR: [Signature]	STATE OF CALIFORNIA <b>DEPARTMENT OF PUBLIC WORKS</b> <b>DIVISION OF ARCHITECTURE</b> SACRAMENTO BY ASSISTANT STATE ARCHITECT: [Signature]	SHEET TITLE: POND, ROAD AND BUILDING LAYOUT PROJECT: CEDAR CREEK EXPERIMENTAL STATION INSTITUTION: DEPARTMENT OF FISH AND GAME LOCATION: APPROX. 20 1/2 MI. NORTH OF LUTHERVILLE, MENDOCINO COUNTY, CALIF.	SHEET 2 OF 3
---	--	--	--	---	-----------------



Estimated  
Completion  
2021-2020



## Lessons Learned

- Engage with agencies early and often
- Important to have both environmental coordinator and the project engineer attend project design/construction discussions with agencies, especially site visits
- Historic site information is important- preserve photos
- Be open to proposed changes
- Hind sight is 20/20




*Photos curtesy of Scott Monday, CDFW*

# Quiota Creek Restoration and Refugio Road Improvements

**Timothy H. Robinson**

**Cachuma Operation and Maintenance Board**

**July 17, 2020**



# The Cachuma Project

## Bureau of Reclamation and Cachuma Member Agencies

Objectives: *(Cachuma Operation and Maintenance Board)*

- Water delivery (reservoirs, tunnels, conduit, etc.)
- Resource management (water and biological species/habitat)



### Watershed:

- ~ 900 sq. mi.
- ~ 90 mi. in length
- 3 reservoirs

# Cachuma Project Elements

- Earthen fill dam with 4 radial gates
- Water supply reservoir only
- Tecolote Tunnel
  - 6.4 miles to transports water through the Santa Ynez Mountains to the South Coast Conduit
- South Coast Conduit
  - 26 miles gravity feed to all South Coast cities (Goleta to Carpinteria)



# Southern Steelhead *Oncorhynchus mykiss*

Listed as endangered  
in 1997



# Southern California Steelhead – Endangered Species List (1997)


## Cachuma Project Biological Opinion (NMFS, 2000): NMFS to USBR

15 Reasonable and Prudent Measures (RPMs):

- Monitoring of the population
- River target flows
- Passage supplementation
- Habitat quality improvement
- Migration barrier fixes
- Reporting
- Outreach
- Adaptive management




# Habitat Restoration Projects




El Jaro Creek – Bank Stabilization



El Jaro Creek – Culvert Replacement



El Jaro Creek – Cross Creek Ranch




Salsipuedes Creek – Hwy 1 Bridge Fish Ladder


Project	Drainage	Timeline
Hilton Creek Watering System	Hilton	2000
Hwy 1 Bridge Fish Ladder	Salsipuedes	2002
Streambank and Side Channel Restoration	El Jaro	2003
Jalama Bridge Fish Ladder	Salsipuedes	2004
Bradbury Dam Flashboard Installation (Surcharge)	Santa Ynez River	2004
Cascade Chute	Hilton	2005
Crossing 6 60-ft Bottomless Arched Culvert	Quiota	2008
San Julian Ranch Fish Ladder	El Jaro	2008
Cross Creek Ranch Fish Passage Improvement	El Jaro	2009
Crossing 2 60-ft Bottomless Arched Culvert	Quiota	2011
Crossing 7 60-ft Bottomless Arched Culvert	Quiota	2012
Crossing 1 60-ft Bottomless Arched Culvert	Quiota	2013
Crossing 3 53-ft Bottomless Arched Culvert	Quiota	2015
Crossing 0A 55-ft Bottomless Arched Culvert	Quiota	2015
Crossing 4 54-ft Bottomless Arched Culvert	Quiota	2016
Crossing 5 58-ft Bottomless Arched Culvert	Quiota	2018
Crossing 9 60-ft Bottomless Arched Culvert	Quiota	2018
Crossing 8 54-ft Bottomless Arched Culvert	Quiota	2019



Bradbury Dam Flashboard Installation



Hilton Creek – Cascade/Chute Passage



Salsipuedes Creek - Jalama Bridge Fish Ladder




El Jaro Creek – San Julian Ranch Fish Ladder



Quiota Creek - Crossing 6

# Quiota Creek Watershed Overview and Plan (2006 – present)



# Summary of all Quiota Creek Projects

#	Projects	Location	Treatment	Designer*	Bridge	Fabricator	Funding	Cost	Year Completed
A	Watershed Plan	-	Road Map	HDR	Contech	COMB + HDR	CDFW + COMB	\$80,459	2000
1	Crossing 6	Refugio Rd	48-ft Bottomless Arched Culvert	HDR	Contech	Bethlehem	Coastal Conservancy + COMB	\$877,627	2008
2	Crossing 2	Refugio Rd	60-ft Bottomless Arched Culvert	HDR	Contech	Jensen	CDFW-FRGP + COMB	\$818,182	2011
3	Crossing 7	Refugio Rd	60-ft Bottomless Arched Culvert	HDR	Contech	Jensen	CDFW-FRGP, WCB + COMB	\$895,102	2012
4	Crossing 1	Refugio Rd	60-ft Bottomless Arched Culvert	HDR	Contech	Bethlehem	CDFW-FRGP, WCB + COMB	\$898,822	2013
5	Crossing 3	Refugio Rd	53-ft Bottomless Arched Culvert	HDR	Contech	PreCon	CDFW-FRGP + COMB	\$922,068	2015
6	Crossing 0A	Ranch Rd	55-ft Bottomless Arched Culvert	HDR	Contech	Bethlehem	CDFW-FRGP, Landowner + COMB	\$788,438	2016
7	Crossing 4	Refugio Rd	54-ft Bottomless Arched Culvert	HDR	Contech	Bethlehem	CDFW-FRGP + COMB	\$1,118,872	2016
8	Crossing 5	Refugio Rd	58-ft Bottomless Arched Culvert	HDR	Contech	Bethlehem	CDFW-FRGP + COMB	\$1,127,737	2018
9	Crossing 9	Refugio Rd	60-ft Bottomless Arched Culvert	HDR	Contech	Bethlehem	CDFW-FRGP + COMB	\$1,210,973	2018
10	Crossing 8	Refugio Rd	54-ft Bottomless Arched Culvert	HDR	Contech	Bethlehem	CDFW-FRGP + COMB	\$1,307,187	2019
11	Crossing 0B	Ranch Rd	?	-	-	-	-	-	?
							<b>Total:</b>	<b>\$10,045,467</b>	
* HDR - Fisheries Design Center									



# Quiota Creek Crossing 8 – Project Specifics


- Project Lead: Cachuma Operation and Maintenance Board (COMB), Tim Robinson
- Stakeholders: COMB, 2 landowners, SB County, CDFW-NMFS, and the public
- Project objective: Remove a fish passage barrier for the endangered southern California steelhead on a NMFS designated critical habitat stream (Quiota Creek, a tributary to the Santa Ynez River)
- Project location: 5 miles south of the town of Santa Ynez, CA (Santa Barbara County)
- Design approval (Santa Barbara County, NMFS, CDFW): 3 years
- Design engineers: HDR Fisheries Design Center
- Bridge design and manufacturer: Contech (O-Series)
- Bridge fabricator: Bethlehem Construction (Wasco, CA) (180 miles from project site)
- Permit acquisition: 8 months
- Contractor: Peter Lapidus Construction
- Biological monitoring: COMB Fisheries Division
- Start date: 9/18/19
- Completion date: 1/8/20
- Instream work completed: 11/15/19
- Total cost: \$1,307,187
- Funding: \$1,010,700 CDFW-FRGP and \$296,457 COMB



# Construction Process

- Survey
- Close the road
- Environmental containment and relocation
- Dewatering
- Clearing, grubbing and
- Concrete crossing removal
- Foundation excavation and pouring
- Bridge fabrication at a pre-fabricator
- Bridge transport and installation
- Backfilling the arches
- Installation of instream elements
- Install anti-graffiti coating
- Road and shoulder work
- Pave road
- Guardrail and bridge rail installation
- Revegetate (plant mitigation trees and hydro-mulch/seed)
- Final inspection

## Biological Monitoring Pre-, During-, and Post-Construction



### Reporting:

- **Progress Reports**
- **Final Report**
- **Annual Performance Evaluation Reports**

# Species Relocation, Dewatering, Clearing/Grubbing and Excavation for Foundations




# Bridge Foundation Construction




# Instream Elements



# Bottomless Arched Bridge – Fabrication



# Concrete Curing Temperature Monitoring (Section 90-4.01D(2)(d))



1. Maximum internal concrete temperature can't exceed 165 degrees F
2. Internal temperature gain can't exceed 40 degrees F per hour

- Measured max temperature: 105 – 115 degrees F
- Smooth curing temperature cures

# Bridge – Transport



# Bridge Installation



# Quiota Creek Crossing 8 Time-elapse Bridge Installation



# Grout, Backfilling, Road/Shoulders, and Pave





# Guardrails and Bridge-Rails



- Standard galvanized Midwest Guardrail System with Caltrans approved inline 31" terminal system and Natina coating
- Modified FHWA California Type 115 bridge rail with single bike rail at 54-inches utilizing corten weathering steel


# Revegetation, Site Cleanup and Reporting



# Public Outreach – ESRI StoryMaps

## Quiota Creek Fish Passage and Habitat Restoration Projects

- The public can see completed projects via StoryMaps embedded on our website
- “Guided Tour” allows text and media to be related to a specific location on the map
- Supports gif format, for professional looking before and after pictures that auto-fade



ArcGIS StoryMaps

10 Quiota Creek Crossing 8 (2020)

**The Problem**


A dilapidated substandard and temporary one lane bridge was placed on top of a damaged concrete low flow crossing over Quiota Creek. The bridge and foundations were vulnerable to failure during high flow events that if collapsed would impede upstream and downstream migration for the endangered southern California steelhead known to inhabit Quiota Creek.

10 / 10

**The Solution**

# Conclusions

- Bottomless arched culvert bridges
- 3-4 month long project
- Good flow conveyance
- Get all permits (Haul) early
- Blend into the background
- Contractor that knows bridge and stream work
- County, landowners and the public
- The fish and aquatic life





# What Can We DO?

## Case Studies: Twin and Ditch Gulches

Eric L. Rulison


California Department of Transportation

North Region-District 2


Office of Environmental Management



# Introduction – Twin Gulches Curve Improvement Project



LOCATION MAP





# Pre-Work





Water Gulch



Trail Gulch outlet




# Design – Trail Gulch



# Design – Water Gulch

**NOTE:**  
FOR ACCURATE RIGHT OF WAY DATA, CONTACT  
RIGHT OF WAY ENGINEERING AT THE DISTRICT OFFICE.


- LEGEND:**
- DRAINAGE SYSTEM No.
  - DRAINAGE UNIT
  - FLOW DIRECTION
- ABBREVIATIONS:**
- GLB GABION LINED BENCH
  - GLC GABION LINED COLLECTOR
  - GLD GABION LINED DITCH
  - TCE Temp CONSTRUCTION EASEMENT



DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
02	Sho	299	4.3/5.5	33	166

12-20-11  
 REGISTERED CIVIL ENGINEER DATE  
 3-12-12  
 PLANS APPROVAL DATE

SHAWN ALEXANDER  
 No. C70833  
 Exp. 30-15  
 CIVIL  
 STATE OF CALIFORNIA



DESIGNED BY: SHAWN ALEXANDER  
 CHECKED BY: MICHAEL FEAKES  
 DRAWN BY: DAVID RYAN  
 DATE: 12/20/11  
 PROJECT: ROUTE 299  
 SHEET: 33 OF 166

# Basic (cont.)


Permits– 401, 404, LSAA, Water Use Permit

Project Lead and involved Organizations: Caltrans, CDFW, ACOE, RWQCB, USFS, UC Davis Road Ecology Center, Nordic Industries

## Planning and Project Delivery:

- Caltrans Functional Units
- Environmental m/w/Agencies
- Environmental m/w Scientists

Caltrans PDT made decisions



# Water Gulch (96" x 155')



# Water Gulch

Outlet



View from outlet into habitat



# Trail Gulch (72"x 204')



# Culvert Enhancements

- Planting
- Mulch

Time



# *Cameras placed at every entrance*



# Wildlife Use

Project Cost - \$17,858,464.78

But the costs of the culverts were minor



104F40C ○ 07-28-201



35F2C ○ 01-02-2015 04:22:55



44T5 ○ 2017-04-12 20:00:02



55F12 ○ 2017-05-21 07:21:06



42P1 ○ 11-28-2016 08:47:15



56P10 ○ 06-21-2017 23:20:03



50F10C ○ 02-13-2015 17:23:49



45F7 ○ 2017-02-20 10:38:05



102F38 ○ 09-08-2017 14:21:07

# CASE STUDY 2

## Ditch Gulch – In Construction (Finished next year)



Trinity County  
State Route 36  
Post Miles 26.7 to 27.1



# Aquatic Organism Passage




# Basics

- Permits– 401, 404, LSAA, Letter of Concurrence (USFWS), Special Use permit
- Project Lead and involved Organizations: Caltrans, CDFW, ACOE, RWQCB, USFS, AECOM

## Planning and Project Delivery:

- Caltrans Functional Units
- Environmental m/w/Agencies
- Environmental m/w Scientists

Caltrans PDT made decisions




NOTES:

- PAINT "D" No. 05-0083
- PAINT "DITCH GULCH BRIDGE"
- CALIFORNIA ST-205 BRIDGE RAIL (Mod)
- MIDWEST GUARDRAIL SYSTEM, SEE ROADWAY PLAN

EVC STA 16+10.00 Elev 3569.49  
 BVC STA 20+55.00 Elev 3565.60  
 -4.48%

**PROFILE GRADE**  
NO SCALE



**DEVELOPED ELEVATION**  
1" = 30'



**PLAN**  
1" = 30'

DESIGNER: LARRY HANDELEY	DESIGNER: D. ALVAREZ	DESIGNER: S. MORIMOTO	DESIGNER: S. MORIMOTO	DESIGNER: S. MORIMOTO	DESIGNER: S. MORIMOTO
DETAILS: S. SILVA / S. MO					
DATE: 03-09-18					


**CHANGE ORDER No. \_\_\_\_\_ SHEET \_\_\_\_\_ OF \_\_\_\_\_**

NO.	DATE	REVISION(S) DESCRIPTION	BY	CHK	DATE
1	03-09-18	Updated Quantities	SM	HT	SS
2	03-09-18	Revised Superlevation	SM	HT	SS
3	03-09-18	Revised Plan	SM	HT	SS
4	03-09-18	Revised Elevation	SM	HT	SS

REGISTERED CIVIL ENGINEER: [Signature] DATE: 03-09-18

NOTES:

- FOR "INDEX TO PLANS", "STANDARD PLANS LIST", "GENERAL NOTES" AND "SPREAD FOOTING DATA TABLE" SEE "INDEX TO PLANS" SHEET.
- FOR "SUPERELEVATION DIAGRAM" AND "CAMBER DIAGRAM" SEE "DECK CONTOURS" SHEET.
- FOR "PILE DATA TABLE" SEE "ABUTMENT DETAILS No. 3" SHEET.




**TYPICAL S**  
3/4" = 1'

**QUANTITIES**

- STRUCTURE EXCAVATION (BRIDGE)
- STRUCTURE EXCAVATION (BRIDGE) (NATURALLY OCCURRING)
- 24" CAST-IN-DRILLED-PILE CONCRETE FILLING
- STRUCTURAL CONCRETE, BRIDGE FOOTING
- STRUCTURAL CONCRETE, BRIDGE
- STRUCTURAL CONCRETE, BRIDGE (POLYMER FIBER)
- JOINT SEAL (MR 2")
- BAR REINFORCING STEEL (BRIDGE)
- BAR REINFORCING STEEL (EPoxy COATED) (BRIDGE)
- PREPARE CONCRETE BRIDGE DECK SURFACE
- FURNISH POLYESTER CONCRETE OVERLAY
- BLACK POLYESTER CONCRETE OVERLAY
- ROCK SLOPE PROTECTION 150 LB. CLASS III, M CALIFORNIA ST-205 BRIDGE RAIL (MODIFIED)

NOTES:

- FOR ACCURATE RIGHT OF WAY DATA, CONTACT RIGHT OF WAY ENGINEERING AT THE DISTRICT OFFICE.



**LINE TABLE**

No.	Δ	R	T	L
1	S 37°42'18" E	55.62'		
2	S 17°41'43" W	34.04'		
3	N 71°12'29" W	56.36'		
4	S 33°30'34" W	75.63'		
5	N 52°11'08" W	54.00'		
6	N 33°30'34" E	75.63'		

**CURVE DATA**

No.	Δ	R	T	L
1	88°56'02"	4.81'	7.76'	
2	91°05'52"	5.10'	7.95'	
3	23°18'18"	81.30'	179.86'	
4	90°00'00"	5.00'	7.85'	
5	90°00'00"	5.00'	7.85'	
6	24°18'18"	81.83'	181.20'	

**CONSTRUCTION DETAILS**  
SCALE: 1" = 50'

# Future work/costs

Cameras will be set to document species use



Thus far... \$9,161,300.69





## Project Benefits, Challenges, and Lessons

- Engage with agencies EARLY and OFTEN
- Engage with the experts
- Conduct site visits
- Pre-project surveys – protocol level (if needed)
- Be adaptable and willing to try different approaches
  - Creating crossings for focal terrestrial species is trial and error
  - Create large viaduct or structure when possible to reduce WVC with LARGE species
- Costs can be inexpensive for CSP culvert in fill slope
- Other design options can optimize and produce a better project



38 – Landscapes with (A) high and (B) low degrees of connectivity. A connected landscape structure typically has higher levels of functions than a fragmented landscape.  
Stream Corridor Restoration: Principles, Processes, and Practices (10/98)  
Federal Interagency Stream Restoration Working Group (FISRWG) (15 Federal agencies of the U.S.)



# California Fish Passage Advisory Committee Connectivity Case Studies

[www.cafishpac.org](http://www.cafishpac.org)

